OFFICE OF THE ENGINEER-IN-CHIEF
P.W.D. NIRMAN BHAVAN, NORTH BLOCK,SECTOR-19
NAWA RAIPUR, ATAL NAGAR (CHHATTISGARH)

AMMENDMENT NO. 14

No. 65011/746 /SOR/ Nawa Raipur, Atal Nagar Dated 27/01/2026

The following ammendments are hereby issued in the items mentioned below in S.O.R. for Building Works (in effect from 01-01-2015)

1. Chapter- 4 – WATER PROOFING

1) Item No. 4.23 & 4.24 is added as given below.

Item No.	Description	Unit	Rate Rs
4.23	Providing and applying on damp/seepage affected wall area with water proofing primer in two coats 1st coat with Acrylic Exterior sealer primer & 2nd coat with Exterior water proof coat elastomeric emulsion primer on all surface 1st coat applied @ 0.75 litrs/10 sqm and 2nd coat applied @ 2.00 litrs/10 Sqmt without any dilution with water as per relevant I.S. code 13435-5:1992 & guidelines as per I.S. 13182 :1991 product such as (Asian paints Truecare Exterior wall primer sealer & Asian paints Smartcare Damp Sheath Exterior, Dulux Weather shield wall primer sealer E900 & Dulux Aquatech Damp protect Basecoat), Nerolac Sealer exterior & Nerolac Prima NoDamp, Berger Homeshield Seal-O-Prime & Damp Stop SP300, Birla opus Perfect start sealer & Birla opus primer water proofing B-300).This priming work shall be carried out after scrapping/removal of old paint/putty properly cleaning the surface with remove loose particle with wire brushes or grinding tools as required and with satisfaction of engineer-in-charge for all height with all tools, tackles and labour etc. complete for the work with Prior Permission of Chief Engineer (Cost of scrapping and removing cleaning of paint is included in this item) (It is recommended that the top coat and this primer should be from same company/manufacturer for minimum 3 year guarantee)	Sqm	115.00

4.24	Providing and applying on damp/seepage affected wall for sealing cracks/joints in the surface with routing out and making U shape grove size 20X20mm (size may increase as per the actual condition) and properly cleaning, removing loose particle with wire brushes or grinding tools as required. Then this grove gone through priming with water proof sealer @ 0.14 Lit / 10mt. further to be filled with ready make crystalline epoxy mortar paste @ 0.50 kg/mt. product such as (Asian paint smartcare crack seal, Dulux Aquatech crackfiller, Nerolac Perma crackfiller, Berger Homesheald crack fill, Birla opus Crack master, Dr. fixit Crac X ShrinkFree) for all height with all tools, tackles and labour etc. complete for the work with Prior Permission of Chief Engineer (Cost of scraping and making as required grove is included in this item)	Meter	225

1. Chapter- 14 – DISTEMPERING, PAINTING AND FINISHING

1) Item No. 14.101.1 & 14.101.2 is added as given below.

Item No.	Description	Unit	Rate Rs
14.101	Providing and applying of water based exterior emulsion modified acrylic paint for kerb stone, pathway divider and cement based surface etc. with excellent adhesion to concrete surface having high DFT U.V.- resistance, fungal resistance, low V.O.C., anti-carbonation coating ensuring long term maintenance and fulfill the requirement of I.S. 164:2023 with manual or machine process as per standard guidelines alternating patterns strip e.g. black and white or yellow and black colour strip product such as (Berger Guideline road & kerb marking R.M. 164 , Asian paints Apex suprema anti carbonation coating) including cleaning the surface with all tools, tackles and labour etc. complete for the work.		
14.101.1	One Coat @ 0.90 lit/10sqm upto final finish	Sqm	55.00
14.101.2	Two Coat @ 1.60 lit/10sqm upto final finish	Sqm	88.00

All above ammendments shall be applicable with immediate effect.

27.1.26

Engineer-In-Chief
Public Works Department
Nawa Raipur, Atal Nagar (C.G.)

Endt. No.65011/746 /SOR/ Nawa Raipur, Atal Nagar Dated 27/01/2026

Copy to the

1. P.A. to Honorable Minister of P.W.D.C.G. Govt. Raipur.
2. Secretary, C.G. Govt. P.W.D. Nawa Raipur Atal Nagar.
3. Secretary, Finance Department C.G. Govt. Nawa Raipur Atal Nagar.
4. All Chief Engineers. P.W.D. Chhattisgarh.
5. All Superintending Engineer, P.W.D. Chhattisgarh.
6. Chief Technical Examiner (V) C.G. Raipur
7. Accountant General, C.G. Raipur
8. All Collectors, Chhattisgarh.
9. All Executive Engineer, P.W.D. Chhattisgarh.
10. Website Public Works Department https://www.cg.nic.in/pwdraipur

27.1.26

Engineer-In-Chief
Public Works Department
Nawa Raipur, Atal Nagar (C.G.)