OFFICE OF THE ENGINEER-IN-CHIEF
P.W.D. NIRMAN BHAVAN, NORTH BLOCK,SECTOR-19
NAWA RAIPUR, ATAL NAGAR (CHHATTISGARH)

AMMENDMENT NO. 12

No. 65011/718 /SOR/ Nawa Raipur, Atal Nagar Dated 19/08/2025

The following ammendments are hereby issued in the items mentioned below in S.O.R. for Building Works (in effect from 01-01-2015)

1. Chapter- 8 - WOOD AND PVC WORKS

1) Item No. 8.183 is added as given below.

Item No.	Description	Unit	Rate Rs
8.183	Providing & Fixing Customized teak wood furniture for Artistic decorative partition, shelves, cabinets of required thickness, length and height with 1st class Bijapur / Batul / Balaghat forest Teak wood (Premium Quality) including carving and 1st class finishing with all tools, tackle and labour etc. complete as per approved design and specifications. (Including Grinding & rubbing all surfaces to smooth finish with gloss/ Matt finish P.U. cleaner polish with following process in the sequence as detailed 1.The surface to be polished is rubbed with sand paper 80/120 no. & then with sand paper of 160/180 nos. 2.Applying two coats of sealer with spray gun and allowing sufficient drying time for 1st coat and 2nd coat is allowed to dry for 8 to 12 hrs. 3.On drying of sealer coat, wet rubbing with emery cloth of finer grading with ample water to remove excess sealer layer and make the surface further smooth after this wet rubbing,then surface is applied with special grade Pu Cleaner Polish to fill all the small and big holes/grooves etc. Filler coat to be allowed to dry for 4 to 6 hrs on which again a light wet rubbing is done this surface is further allowed to dry for 12 hrs. 4.On this, 1st coat of Pu Cleaner Polish polish is applied with spray gun using Pu Cleaner Polish clear polishand Pu Cleaner Polish thinner in required proportion. This 1st coat is allowed to dry for 24 hrs then this dry surface is again fine wet rubbed smooth, which is further allowed to dry for 12 hrs.The final Pu Cleaner Polish polish is applied with compressor pressure spray gun using Pu Cleaner Polish clear polish and Pu Cleaner Polish thinner mixed in required proportion complete as per direction of Engineer-in-Charge.	Cum	6,87,078.00 **

Note - **These items shall be executed only with prior permission of Engineer in Chief P.W.D. Nawa Raipur Atal Nagar, Chhattisgarh.

All above ammendments shall be applicable with immediate effect.

19/8/2025

Engineer-In-Chief
Public Works Department
Nawa Raipur, Atal Nagar (C.G.)

Endt. No.65011/718 /SOR/ Nawa Raipur, Atal Nagar Dated 19 /08/2025

Copy to the

1. P.A. to Honorable Minister of P.W.D.C.G. Govt. Raipur.
2. Secretary, C.G. Govt. P.W.D. Nawa Raipur Atal Nagar.
3. Secretary, Finance Department C.G. Govt. Nawa Raipur Atal Nagar.
4. All Chief Engineers. P.W.D. Chhattisgarh.
5. All Superintending Engineer, P.W.D. Chhattisgarh.
6. Chief Technical Examiner (V) C.G. Raipur
7. Accountant General, C.G. Raipur
8. All Collectors, Chhattisgarh.
9. All Executive Engineer, P.W.D. Chhattisgarh.
10. Website Public Works Department https://www.cg.nic.in/pwdraipur

Engineer-In-Chief
Public Works Department
Nawa Raipur, Atal Nagar (C.G.)