OFFICE OF THE ENGINEER-IN-CHIEF

P.W.D. SIRPUR BHAVAN RAIPUR (CHHATISGARH)

,AMENDMENT NO. 02

The following amendments are hereby issued in the items mentioned below in S.O.R. for Road Works (in effect from 01-01-2015)

1. Chapter-4

1) Item 4.15 (E&F) is added as given below.

2. Chapter-6

1) Item 6.8 (A&B) is added as given below.

4.15 (E)	**Removing of existing laid 60mm/80mm thick precast interlocking concrete paver blocks without any damaged in any shape and pattern, over coarse sand bed with stacking of block in proper manner with in the lead of 100.00 mt inclusive of all labour etc. complete the work.**	Sqm	36.00
4.15 (F)	**Laying only of paver block 60mm/80mm thick precast interlocking concrete blocks in any shape/pattern, including and over 50 mm thick average coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete for the work.**	Sqm	104.00
6.8	**Construction roller compacted concrete pavement over a prepared sub-base, coarse and fine aggregate conforming to IS:383, and graded as per table 600-3, mixed as per approved mix design at site, laid, spread, vibrated, compacted with vibratory roller of the double drum wheel type (80-100 kn) and finished in a continuous operation including separation membrane, sealant primer, joint sealant, de-bonding strip, admixtures as approved, curing compound, finishing to lines and grades as per drawing (as per IRC SP:68-2005)**		
	A) With Cement concrete grade M-40 and minimum cement content @ 400 kg/cum.	cum	4908.00
	B) With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum.	cum	4739.00

All above amendments shall be applicable with immediate effect.

Engineer-in-chief
P.W.D. Raipur (C.G.)

Endt. No. 6501008 3 / 295 / पी-डी-डी/15 Raipur, Dated 13/06/2016

Copy to the

1. P.A. to honorable Minister of P.W.D.C.G. Govt. Raipur.
2. Principle Secretary, C.G. Govt. P.W.D. Raipur.
3. Secretary, Finance Department C.G. Govt. Raipur
4. Director General "Road Development". Shipping, Transport and Highway Mantralaya. Transport Bhawan Sansad Marg, New Delhi 11001.
5. All Chief Engineers. P.W.D. Chhattisgarh.
6. All Superintending Engineer, P.W.D. Chhattisgarh.
7. Zonal Officer, Road Transport & Highway Satpuda Bhawan Bhopal (M.P.)
8. R.O. National Highway Complex Raipur (C.G.)
9. Chief Technical Examiner (V) C.G. Raipur
10. Accountant General, C.G. Raipur
11. All Collectors, Chhattisgarh.
12. All Executive Engineer, P.W.D. Chhattisgarh.
13. Executive Engineer, Nagar Nigam Raipur.

Engineer-in-chief
P.W.D. Raipur (C.G.)